

Mechanical Support Group High Energy Physics Division Argonne National Laboratory

Victor Guarino P.E.

Group Leader - Mechanical Engineer




Mechanical Support Group Capabilities

Victor Guarino

HFP-ANI

- Project Management
- Structural analysis
- Finite Element modeling
- 3D solid modeling and 2D drafting
- Mechanical construction
 - Fabrication
 - Fixturing
- Machine design
- Civil Construction
- Fiber optics
- Material testing
 - Creep testing
 - Bolt strength testing
- Automatic control systems
- Safety Analysis
- Hydraulics
- Ultra-High Vacuum
- Machine Shop Services






Current Experiments

- Tile Calorimeter in ATLAS at CERN
- MINOS
- CDF Upgrade
- □ NOVA
- CHOOZ2
- Wakefield
- Auger
- Veritas
- DES



Atlas

- Supervised the fabrication of raw steel plates. (80,000 5mm thick steel plates stamped in Czech Republic using US die)
- Supervised the fabrication of welded girder in Spain which acts as main structural support.
- Constructed 65 Extended Barrel modules.
- Instrumented 65 Extended Barrel modules
- Performed the complete structural analysis for ATLAS Tilecal
- Responsible for the design and implementation of the ATLAS moving system.
- Participating in support service installation
- Working with Technical Coordination on brackets and supports.






ATLAS Structural Analysis

ATLAS Tile Calorimeter Support Structure High Energy Physics Division, Argonne National Laboratory



Argonne's High Energy Physics Division is collaborating on the LHC ATLAS experiment and was responsible for construction of a large fraction of the Extended Barrel Tile Hadron Calorimeter. HEPD is making a unique contribution to the experiment in terms of providing engineering design and analysis of much of the support structure of the calorimeter; the "saddles" on which the cylinders rest and the link plates which connect modules together. The resulting structure is entirely self-supporting.




This schematic shows the main elements of the saddle One pair of these is used to support each Extended Barrel cylinder, which is imetely 2.7m in length and 2 pairs of saddles are used to support the Barrel cylinder, which is 6m



33mm diameter pins in the connecting plates between modules carry the tension load below th saddles which regists the moment from the module



Modules in the region of the saddles simply rest on awinel halts which are mounted in the holes shown



ilts from the local load of the endcap calorimeter which is itself support of

Finite element analysis



A full pre-assembly of each cylinder will be carried out prior to final assembly in the ATLAS caven

The first of these is shown here. The assembled cylinder is itself over Bm high, weight 640 tons and sits on 2 pairs of blocks below each of



A special module for which connecting plate is a single piece has a key which sits in the slots shown in the saddle. The key carries the vertical shear load in the ATLAS support rails.

FURTHER INFORMATION: Argume ATLAS Projects: gate,hap and gov/lorice/atlas/atla ATLAS Experiment: stlus, web.com.ch/Atlas/Welcoms.html


TileCal COLLABORATORS

Argonne National Laboratory plus institutions from Armenia, Brazel Belarus, Cooch Republic, France, Greece, Italy, Poetugal, Romania, Russia, Spain, Sweden, Slovak Republic, and the United States



ATLAS Movement system fully functional and being used for EC Movements April '06-'07

- □ System was used to close-up the End-Caps in preparation for the magnet test during the summer.
- The automatic leveling system was successfully tested during the EC movements and is complete.
- The guided service line and Liquid Argon Safety line interfaces were tested.
- □ Since August '06, the CERN staff has independently made several movements of End cap.






Expanding the Movement system for remaining detector systems

April - December '07

- Minor modifications needed to extend the system to move JD (small wheel), Toroid End Cap
- Additional hardware and logic to be added for HF truck movement with integrated gripping cylinder
- Integrate Big Wheel movement system into overall control system. Add tilt control of shielding





MINOS

- Designed and fabricated the production equipment used to fabricate modules
 - Scintillator cutting station
 - Forming Station
 - Assembly trays
 - Module curing racks
 - Fiber gluing machine
 - Connector flycutter
 - Module Source Mapper
- Fabricated near detector modules
- Helped to design module components
- Performed R&D on Scintillator extrusions



Fiber Gluing Machine

- PLC controlled semiautomatic operation
- Applies epoxy, fiber, and tape in single operation
- Operator controls on both sides of carriage
- Accommodates 8 different type of module geometry
- Fiber and glue dispensing tracks scintillator groove




Victor Guarino HEP-ANL



Astro-Experiments

- Performed extensive thermal and structural analysis on DES
- Collaborating with UCLA on developing conceptual designs for a 20m Veritas upgrade telescope.
- Collaborating with UCLA on a conceptual design for a new aplanatic two-mirror telescope.





CDF Upgrade

- Designed and constructed CPR and CCR modules.
 - Optimized design for minimum deflection with maximum scintillator volume.
 - Developed fixturing and assembly techniques for efficient production
 - Mounting details
 - Tests of bond strengths, bond creep, module deflection
- Constructed 56 CPR modules, 56 CCR modules









NOvA PVC R&D

- Leading the R&D of PVC composition to optimize reflectivity and minimize creep.
- Conducting tests on materials
- Constructed a 27ft. x 15ft. Four plane prototoype to test construction methods.
- Conducting PVC and epoxy evaluations.












Long Term creep tests at ANL


- ASTM samples are instrumented with strain gages
 - Gages cancel bending
- Samples under test
 - N2 6 samples 213 days (2 each nominally at 300,500, 700 psi)
 - N23 5 samples 97 days (300 [1], 450 [2], 650 [2] psi)
 - N24 5 samples 80 days (300 [1], 500 [2], 700 [2] psi)
- Temperature controlled box constructed
 - Temperature is 20.4 +/- 0.3 °C
 - Manual humidity control. Goal is 50% but excursions to 20% occur.
 - Unloaded control sample included and use humidity corrections







N2 (213 days), Nova 24 (97 days), N23 (80 days) compared to PET-B (most conservative) prediction






NOVA

- Taking a leading role on the structural design, design and fabrication of assembly equipment, the evaluation of adhesive, and the development and evaluation of the required PVC.
- Responsible for the design of the IPND and its required fixturing and assembly tooling.
- Evaluating ES&H and designing a filtering system for handling VOC's from Adhesive





Victor Guarino HEP-ANL




NOVA

Adhesive and Extrusion Testing

- Performing extensive evaluation of adhesive.
- Testing adhesive using standard ASTM tests as well as glued extrusions.
- Constructing prototypes small scale prototypes instrumented with strain gages to directly measure stresses and compare them to calculations.
- Worked with adhesive vendor to develop a custom adhesive.









Victor Guarino HEP-ANL



NOvA Structural Analysis and Assembly

- L3 manager on structural analysis, assembly equipment and tooling, and adhesive R&D.
- Leading the design of the IPND
- Contributing to the Civil Engineering








NOvA ES&H

- Adhesive releases Methyl-Methacylate.
- Working with ANL Industrial Hygeine to monitor vapors during production.
- Working ANL IH to determine the generation rate of MMA in order to properly design a ventilation system.







NOVA Upcoming Work

- A full size (53ft x 53ft) assembly prototype will be constructed at ANL.
- The IPND modules will be constructed at ANL.
- The full height prototype will be constructed at ANL and shipped to Fermi for installation and testing.



Wakefield

- Provide engineering services
- Technician support.







AUGER

- Developed design and fabricated prototype module.
- Designed and fabricated fiber cookie.
- Glued and routed fibers in scintillator strips.









Victor Guarino HEP-ANL




ILC

- Working on RPC design and method of fabrication.
- Constructing SLICE test and 1m² test
- Detector design.
- Civil construction









Machine Shop

- Full Service Machine Shop
- □ Prototype, fixture, part fabrication.



Victor Guarino HEP-ANL



Conclusion

- Mechanical engineering and construction are central to the success of any HEP experiment today.
- ANL is in a position to provide major mechanical engineering and construction of the larger components of an experiment to complement the work of university collaborators.
- The Mechanical Support group has a broad range of skills and capabilities needed by high energy physics.
- ANL Mechanical Support has been a central component of the success of ANL's past experiments and are at the center of much of the work of exploring and preparing for the next generation of experiments.